



iGMAS Update and Status

DONG Xurong SUN Hanrong LU Xiaochun

OUTLINE

I iGMAS Construction

II iGMAS M&A Results

III iGMAS Announcement



iGMAS Construction



iGMAS Tasks

Establish global real-time tracking network, which could track the whole orbits of BDS, GPS, GLONASS and Galileo satellites, as well as platform with data collection, storage, analysis, management, publishing abilities. This platform would monitor and assess the GNSS operational status and key indicators, then generate precise ephemeris, Earth Orientation Parameters, station coordinates and speed, global ionospheric delay and GNSS integrity to support satellite navigation technology test, monitoring and assessment, service in scientific research and various applications.




iGMAS Construction



System Components

- 30+ tracking stations;
- 4 signal monitoring stations;
- 3 data centers;
- 8 analysis centers;
- 1 monitoring and assessment center;
- 1 product integration and service center;
- 1 operational control and management center.






iGMAS Construction



Procedure

Stage 1: 2011-2014, built 20 tracking stations, 2 data centers, 5 analysis centers, 1 monitoring and assessment center, 1 product integration and service center, 1 operational control and management center.






iGMAS Construction



Stage 2: 2014-2016, build more 10 tracking stations, 1 data center, 2 analysis centers, and update the system for more stations processing ability.






iGMAS Construction



Stage 3: 2016-2020, update system to have next generation BDS processing ability.





iGMAS Construction



Milestones

- Sep. 2007, idea of iGMAS;
- Aug. 2010, requirements analysis and project approachment;
- Mar. 2011, first proposed concept of iGMAS;
- Dec. 2012, iGMAS project approval;
- May 2013, start of iGMAS construction;
- Jan. 2014, start of integration testing;
- Jul. 2014, start of trial running.



iGMAS Construction



GNSS Receiver

Unicore, CETC 54 and CETC 20 have finished production of multi-GNSS receivers, some of them have been installed on stations.



Unicore



CETC54



CETC20



iGMAS Construction



Tracking Stations

- Infrastructure construction of 8 domestic stations have been completed, receiver equipments have been installed.



BeiJing



LASA




Urumqi



Chang Chun



Kun Ming



Shang Hai



Wu Han



Xi'an



iGMAS Construction



- Arctic and Antarctic stations infrastructure construction have been completed and equipped with receiver and network equipment.
- Several stations outside China, e.g. in Pakistan have been equipped with receiver and network equipment.
- Stations in Russia, Germany, England and South Africa are progressing.



iGMAS Construction



Signal monitoring station

- Apr. 2009, an 7.3m antenna started to work in Xi'an;
- Oct. 2014, an 40m antenna was put into service in Xi'an;
- International cooperation with Canada, Malaysia and Argentina for signal quality monitoring and assessment has been determined.





iGMAS Construction



Construction of Centers


- 3 data centers have finished internal integration testing;
- 10 analysis centers have finished internal integration testing;
- Monitoring and assessment center, operational control and management center, product integration and service center have finished internal integration testing;
- iGMAS has started trial running since July, 2014.




iGMAS Construction



- Data Center



NUDT



WHU



NTSC



iGMAS Construction



数据中心NTSC - CMCB@10.12.5.10 - FileZilla

文件(F) 编辑(E) 查看(V) 传输(T) 服务器(S) 书签(B) 帮助(H) 有新版本了!(O)

主机(H): 用户名(U): 密码(W): 端口(P): 快速连接(Q)

本地站点: C:\Users\Administrator\Desktop\NTP | 远程站点: /pub/normaldata/data/iGMAS/BDT/2014/112/hourly/00


文件名 文件大小 文件类型 最近修改 权限 所有者/组

文件名	文件大小	文件类型	最近修改	权限	所有者/组
uncr112a_14e.Z	48,120	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
uncr112a_14g.Z	4,780	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
uncr112a_14i.Z	346,297	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
uncr112a_14k.Z	409	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
uncr112a_14l.Z	230	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
uncr112a_14m.Z	2,179	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
uncr112a_14n.Z	7,028	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
uncr112a_14r.Z	5,545	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
uncr112a_14t.Z	24,940	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14a.Z	62,561	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14d.Z	729	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14e.Z	20,712	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14g.Z	156	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14i.Z	363,613	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14j.Z	59,241	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14k.Z	278	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14l.Z	245	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14m.Z	1,608	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14n.Z	252	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14r.Z	2,854	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
vuh1112a_14t.Z	11,346	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
zhon112a_14a.Z	517,021	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
zhon112a_14d.Z	84,037	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
zhon112a_14e.Z	31,187	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
zhon112a_14g.Z	2,381	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
zhon112a_14i.Z	217,681	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
zhon112a_14j.Z	128,157	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
zhon112a_14k.Z	271	好压 Z ...	2014/4/22 1:11:00	-rw-r--r--	500 500
zhon112a_14l.Z	57,959	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
zhon112a_14m.Z	1,616	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
zhon112a_14n.Z	3,739	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
zhon112a_14r.Z	2,449	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500
zhon112a_14t.Z	206	好压 Z ...	2014/4/22 1:12:00	-rw-r--r--	500 500

5个文件。大小总共: 4,926,195 字节 123 个文件。大小总共: 6,236,323 字节

响应: 150 Here comes the directory listing
响应: 226 Directory send OK
状态: 列出目录成功

失败的文件 成功的传输(24) 消息日志 队列: 空



Data directory



iGMAS Construction



- Analysis Center



Xi'an Satellite Control
Center



Shanghai Astronomical
Observatory



Information Engineering
University



Chang'an University




Space Information
Relay and Transmission
Technology Research
Center



Beijing Aerospace
Control Center



Chinese Academy of
Surveying & Mapping





Institute of Geodesy
and Geophysics



iGMAS Construction



- Monitoring and Assessment Center







iGMAS Construction



- Operational Control and Management Center





iGMAS Construction



- Product Integration and Service Center



OUTLINE

I iGMAS Construction

II iGMAS M&A Results


III iGMAS Announcement



iGMAS M&A Results



Core Products







iGMAS M&A Results




Constellation Status (2014)




BDS Satellites Availability



GPS Satellites Availability



GALILEO Satellites Availability




GLONASS Satellites Availability





iGMAS M&A Results



Quality of Signal-in-space(2014)




User-Received Signal Level




waveform of baseband signal




iGMAS M&A Results




modulation error of carrier phase(April)



signal correlation(August)



signal ranging value stability



Carrier phase value stability

ERROR: undefined
OFFENDING COMMAND: rest

STACK:

-SaveLevel-